S E R I E S S T A N D A R D S:

SEA STACK SERIES

Ranging in size from very small islands to sheer columns of rock, sea stacks appear to erupt from the sea floor. This icon of the Northwest seacoast inspired the strong sense of form the Sea Stack Series. Simple heavy steel roofs (3/16ths" steel) patinated to a rich matt copper brown or coated with a raw bronze that can be patinated and waxed to create a variety of textured finishes. The posts are as strong and damage resistant as they are beautiful using either Brazulian Cherry joined at the corners with a double rabbit that leaves a distinctive and extraordinarily stone inset edge. At night this series shines like no other. The diameter of light can be 100 feet at .5 lm while the diodes are completely hidden, or a portion of them can be directly on the post to give a point of light as well as extend the light radius.

Sea Stack I: H - 24" Roof - 8/25" sq Post 2.75" sq														
SEA STACK I	**Material**				**L.E.D.**	**Finish for roof and steel post**				**Wood**	**Ground Attachment**			**Wattage**
Quantity	Steel Roof		Post 2.5"x16"-24"		1,200 lm 25' radius	Patina copper brown	Natural Rust	Textured Steel	Textured Bronze	Oiled Wood	Ground	Slab	Deck	18w VDC
	8.5"	10.5"	Steel	Brown Cherry										

Sea Stack II: H - 36" Roof - 12" sq Post 4" sq													
SEA STACK II	**Material**			**L.E.D.**	**Finish for roof and steel post**				**Wood**	**Ground Attachment**			**Wattage**
Quantity	Steel Roof	Post 4"x24"-30"		1,716 lm 40' radius	Patina copper brown	Natural Rust	Textured Steel	Textured Bronze	Oiled Wood	Ground	Slab	Deck	26w VDC
	12"	Steel	Brown Cherry										

Sea Stack III: H - 48" Roof - 18" sq Post 5.5" sq														
SEA STACK III	**Material**				**L.E.D.**	**Finish for roof and steel post**				**Wood**	**Ground Attachment**			**Wattage**
Quantity	Steel Roof	Post 5.5"x30"-36"			2,650 lm 50' radius	Patina copper brown	Natural Rust	Textured Steel	Textured Bronze	Oiled Wood	Ground	Slab	Deck	31w VDC
	16"	Steel	Brown Cherry	Stone										

OK (click here to confirm and mail)